Jones & Henry
ENGINEERS, LTD.

Village of Oak Harbor, OH
WWTP Improvements

ADDENDUM 4

November 2, 2026

Planholders on the Village of Oak Harbor, OH, WWTP Improvements are hereby notified of the following amendments to the Contract Documents. This Addendum is hereby made a part of the Contract Documents

DRAWINGS

On Sheets C-102.1 and C-102.2, add the following note: “Existing pavement areas shown to be milled shall be milled to a depth of 3 inches. New pavement over milled areas shall be 1 1/4 inch ODOT Item 441 Asphalt Concrete Surface Course (448) and 1 3/4 inch ODOT Item 441 Asphalt Concrete Intermediate Course (448)”

On Sheet C-0.4 Add the following Note: “Trench cuts through existing pavement shall match the existing pavement removed with the surface courses matching the two replacement surface courses described in the Entry Road Pavement Section.

An updated Table of Contents will be included in the Issued for Construction Project Manual.

RECEIPT OF THIS ADDENDUM MUST BE ACKNOWLEDGED ON PAGE C-410-1 OF THE BID.